

Specifications On The A-1 Buildings Post Frame Building

- COLUMNS:** ~~3 ply treated 2 x 6 laminated~~ posts will be set in concrete with 1/2" steel rod thru post.
3 ply Pre Engineered
 - SPLASH BOARDS:** 1 - 2 x 8 treated splashboard will be used at the base of sidewalls.
 - GIRTS:** 2 x 4 girts (side supports for walls) will be set 24" on center.
 - TRUSS SUPPORT:** Posts will be notched, trusses set in notch and secured with 1/2" bolts and ring shank nails.
 - ROOF PURLINS:** 2 x 4 roof purlins will be set on edge, only 20" on center and secured with 6" ring shank nails and tied together with 16 penny nails.
 - SIDE & ROOF STEEL:** All roof and wall metal will be one piece (full length), secured with neoprene washered screws (19 colors to choose from).
ONE PIECE METAL ELIMINATES THE #1 CAUSE OF ROOF LEAKS. NO LAPS ON OUR ROOF METAL LIKE OUR COMPETITION.
 - SEALERS:** Die cut foam sealers will be used at ridge gap.
 - RIDGE LITES**
 - Complete building will be trimmed with choice of 19 colors including rodent barrier at base of sidewall metal.
 - GUTTERS:** Will be installed with downspouts.
 - DOORS:** Sliding doors will be 2" square frames, metal secured with self drilling screws. Overhead doors will be purchaser's choice of steel or fiberglass.
- INSTALLED AND SERVICED BY OUR OWN OVERHEAD DOOR DIVISION**
- All 2 x 4 framing are #1 yellow pine.
 - All of our posts are built out of kiln dried lumber (won't shrink and separate like our competition)

These **Buildings** are built to fit your needs. Check the other features available to make the building you want.

- Overhead Doors
- Roof Vents
- Custom Store Fronts
- Windows
- Ridge lites
- Concrete
- Overhangs
- Post Protectors
- Metal Liner Panel
- Lean to

Why Pay For Less When You Can Have More

